

WORK READY TRUCKS

2020 WESTERN STAR 4700 BIG-MAX CRO-35T CABLE HOIST ROLL OFF PACKAGE

VEHICLE SPECIFICATIONS

- Western Star 4700 set back front axle
- Detroit DD13 engine 12.8L, 505 HP at 1625 RPM
- 1850 lb/ft at 975 RPM
- Eaton/Fuller RTLO-18918B transmission
- 20,000 lbs FGAWR, 46,000 lbs RGAWR
- GVWR 66,000 lbs
- White day cab

EQUIPMENT SPECIFICATIONS

- Carries up to 22' bin, 35 ton capacity
- 12" x 4" x 0.250" HSS tube construction standard, inside/outside rails
- 7" diameter 156" stroke three stage hard chrome-plated pull-on/push-off reeving cylinder
- Removable and greasable bolt-on sheave head assembly
- 5" bore x 78" stroke 3" chromed rod double acting lift cylinders
- Heavy duty greasable 2-1/2" pin hinge block assembly
- 50 gallon frame mounted hydraulic oil tank complete with sight glass, temperature gauge and remote mounted return filter
- Premium in-cab four-way air control console comes with PTO switch in dash, light and proximity switch warning light for rails up alert
- Outside valve bank controls, hoist reeving cylinder and up-down control, handles included
- C-1045 greasable alloy pins at all wear points
- Heavy duty transport safety chain for tie downs and strap back up if required - winch included
- Two position adjustable bin locks at front with adjustable dimension setting
- LED lighting at rear bumper complete with sealed wiring harnesses
- TG series PTO
- Roll Rite DC350 hydraulic tarp system with remote control
- 75,000 lb tow apron (no pintle) - rear apron for future tow capability
- Drivers side aluminum storage tool box 36" W x 24" H x 20" D
- Aluminum checker custom tandem fenders
- Unit sandblasted, primed and painted black

For internal use and reference only!